

# DAKTRONICS QUOTE # 602184-1-0

Camdenton R-III School District  
 Tim Hadfield  
 SOUTH HIGHWAY 5  
 Camdenton, MO USA  
 Phone: (573)346-9231  
 Fax: (573)346-5651  
 Email:

9/Jan/2017  
 Quote valid for: 90 days  
 Terms: 30% with the order, 60% Payment  
 before shipment, 10% Net 30 days from  
 shipment  
 FOB: DESTINATION  
 Delivery: Call for production time

Reference: Football & Basketball Video Options  
 All pricing in accordance with Education Plus Contract #AEPA IFB #016-I.

Item No.	Model	Description	Qty	Price
1	DVX-1130-15HD-N-HC-288x504-120BR-LT-MR-CNTRLR-None	LED Video Display  Matrix: 288 lines by 504 columns Line Spacing: 15mm LED Color: RGB- Cabinet Dimensions: 14' 8" H X 25' 6" W X 0' 8" D (Approx. Dimensions) Max Power: 10118 watts/display Weight: Unpackaged 3931 lbs per display; Packaged 6552 lbs per display	1	\$392,272.00
	Paint: Semi Gloss Black Borders only		80	
	Daktronics System Installation Drawings >100	Attachment support system drawings	1	
	Daktronics System Electrical Drawings >100	Power and control system drawings	1	
	Daktronics System Certified Structural Drawings >100	Engineered stamped drawings for footing and beams	1	
	Control-4 video inputs-SD/HD (Primary/Backup Player & Processor) w/ Laptop	4 video inputs with TriCaster 460	1	
	Camera Kit - Basic SD (Wired)	Sony HXR-MC2500--Standard Definition	3	
	Control room headset kit - Wired		1	
	Headset kit (Wired)	Must have Control room headset kit to include this option.	3	
	Standard Video All Sport® and DakStats RTD Input Kit	Displays Game-In-Progress and Requested Stats Information	1	
	Computer, Laptop	Laptop for DakStats	1	
	Custom RTD Frames -- Single Color Background	Custom, Single Color Background RTD Frames, No Logos. 1-3 RTD Frames	1	
	Team Spirit Football Animations - 20	Personalized Package - Your School Colors, Mascot/Logo - Touchdown, 1st Down, Defense, Great Play, etc.	1	
	Sponsor Feature - Static	Sponsors will choose which in-game event or feature to sponsor - still file with no movement	4	

## DAKTRONICS QUOTE # 602184-1-0

Sponsor Feature - Animations	All Sponsor Logos are featured seperately using a style/template.	4
Sponsor Logo - Static	All Sponsor Logos are featured seperately using on style/template - still file with no movement	4
Sponsor Logo - Animations	All Animated Sponsor Logos are featured separately using one style/template	4
W-1490	Fiber Optic Cable; 50 µm Multimode; 12 Fiber with non-terminated ends	1000
DA-1000-14	Sq Truss; Alum, 2 ft tall x 14 ft long w/ 50% Lettering/Logo & Screen Backing.	1
DA-1000-18	Sq Truss; Alum, 2 ft tall x 18 ft long w/ 50% Lettering/Logo & Screen Backing.	1
Custom DA-1000	Sq Truss; Alum, 2 ft 0 in tall x 25 ft 6 in long (435lbs)	1
LED Backlit Camdenton Lakers Logo; 7'-0" x 14'-10"	LED Backlit Camdenton Lakers Logo; 7'-0" x 14'-10"	1
OB-STATIC ID	Backlit sponsor panel 42" x 306" - 714 lbs each: bottom panel	1
CUSTOM SEPARATE BACKLIT AD PANELS TO MATCH SCOREBOARD LENGTH	Backlit sponsor panel 4.8 ft tall x 7.95 ft wide - 305 each: top panel flanking FB-2504	2
FB-2504-W-PV-R	PanaView® Modular Football Scoreboard; Clock Section; Scoreboard Color: _____; Caption Color: _____ Digit Type: PANAVIEW Digit Color: WHITE Max Power: 350 watts/display Weight: Unpackaged 230 lbs per display; Packaged 484 lbs per display	1
Stripe; Modular Football	Stripe for Modular Football Sections	1
120VAC Trumpet Horn #55	For Outdoor Scoreboards	1
Radio Receiver	Frequency of 2.4 GHz	1
Outdoor Scoreboard Fiber Communication	Communication Type: Fiber (Cable not included) - Back-up option to Radio	1
TI-2003-A-PV for Delay of Game	PanaView® Delay of Game Timer; Set of 2; Scoreboard Color: _____ Cabinet Dimensions: 3' 0" H X 4' 0" W X 0' 8" D (Approx. Dimensions) Digit Type: PANAVIEW Digit Color: AMBER Max Power: 150 watts/display Weight: Unpackaged 65 lbs per display; Packaged 120 lbs per display	1
ID_36x48_O	3' x 4' non-backlit sponsor panel	2
AS-5010 Kit	All Sport® 5010 Control Console Kit	1
Outdoor Scoreboard Radio Communication (Transmitter)	Frequency of 2.4 GHz	1
Radio Receiver	Frequency of 2.4 GHz	2

## DAKTRONICS QUOTE # 602184-1-0

Angle Clamp Mounting Method (A)	For 2 Tubes	1
FREIGHT	Shipping to site via Independent Carrier	1
Physical Installation	See attachment A.	1
System Startup	Final Commissioning of Equipment	1
<b>Services</b>		
<b>2</b>	<b>Warranty &amp; Services</b>	<b>1</b>
P1G5 - 1 Year Platinum, Additional 4 Years Gold Extended Service for 602184-1-0 Main Equipment	1 Year Parts and Labor, Additional 4 Years Parts Extended Service for 602184-1-0 Main Equipment. Includes 45' lift and normal business hours labor. Reference SL-04703 for Platinum scope of services and SL-05659 for Gold scope of services.	1
Standard Video with Tricaster On-Site Training		1

<b>Total Price Excluding Sales Tax: \$392,272.00</b>
--

Please reference listed sales literature: DD1757027 for TI-2003-A-PV for Delay of Game, DD1923159 for Control-4 video inputs-SD/HD (Primary/Backup Player & Processor) w/ Laptop, DD1936413 for Standard Video All Sport® and DakStats RTD Input Kit, DD2216211 for FB-2500-W-PV-R, DD2216211 for FB-2504-W-PV-R, DD2259498 for DVX-1130-15HD-N-HC-288x504-120BR-LT-MR-CNTLRM-None, DD2356684 for DVNMC-144X432-6-RGB-SF-120VAC-MA-MN-WS-MR, DD2563729 for Custom RTD Frames -- Single Color Background, DD2568960 for Sponsor Feature - Animations, DD2568960 for Sponsor Feature - Static, DD2568960 for Team Spirit Basketball Animations - 20, DD2568960 for Team Spirit Football Animations - 20, SL-03991 for AS-5010 Kit, SL-04370 for Outdoor Scoreboard Radio Communication (Transmitter), SL-04370 for Radio Receiver, SL-08027 for Custom DA-1000, SL-08027 for DA-1000-14, SL-08027 for DA-1000-18

Please reference listed shop drawings: DWG 1107197 for DVNMC-144X432-6-RGB-SF-120VAC-MA-MN-WS-MR

DRAFT

# DAKTRONICS QUOTE # 602184-1-0

## Alternate Equipment: 1

Item No.	Model	Description	Qty	Price
1	DVX-1130-15HD-N-HC-288x504-120BR-LT-MR-CNTLRM-None	LED Video Display	1	\$390,642.00
		Matrix: 288 lines by 504 columns Line Spacing: 15mm LED Color: RGB- Cabinet Dimensions: 14' 8" H X 25' 6" W X 0' 8" D (Approx. Dimensions) Max Power: 10118 watts/display Weight: Unpackaged 3931 lbs per display; Packaged 6552 lbs per display		
	Paint: Semi Gloss Black Borders only		80	
	Daktronics System Installation Drawings >100	Attachment support system drawings	1	
	Daktronics System Electrical Drawings >100	Power and control system drawings	1	
	Daktronics System Certified Structural Drawings >100	Engineered stamped drawings for footing and beams	1	
	Control-4 video inputs-SD/HD (Primary/Backup Player & Processor) w/ Laptop	4 video inputs with TriCaster 460	1	
	Camera Kit - Basic SD (Wired)	Sony HXR-MC2500--Standard Definition	3	
	Control room headset kit - Wired		1	
	Headset kit (Wired)	Must have Control room headset kit to include this option.	3	
	Standard Video All Sport® and DakStats RTD Input Kit	Displays Game-In-Progress and Requested Stats Information - DakStats Football	1	
	Computer, Laptop	Used for DakStats	1	
	Custom RTD Frames -- Single Color Background	Custom, Single Color Background RTD Frames, No Logos. 1-3 RTD Frames	1	
	Team Spirit Football Animations - 20	Personalized Package - Your School Colors, Mascot/Logo - Touchdown, 1st Down, Defense, Great Play, etc.	1	
	Sponsor Feature - Static	Sponsors will choose which in-game event or feature to sponsor - still file with no movement	4	
	Sponsor Feature - Animations	All Sponsor Logos are featured seperately using a style/template.	4	
	Sponsor Logo - Static	All Sponsor Logos are featured seperately using on style/template - still file with no movement	4	
	Sponsor Logo - Animations	All Animated Sponsor Logos are featured seperately using one style/template	4	
	W-1490	Fiber Optic Cable; 50 µm Multimode; 12 Fiber with non-terminated ends	1000	

## DAKTRONICS QUOTE # 602184-1-0

DA-1000-14	Sq Truss; Alum, 2 ft tall x 14 ft long w/ 50% Lettering/Logo & Screen Backing.	1
DA-1000-18	Sq Truss; Alum, 2 ft tall x 18 ft long w/ 50% Lettering/Logo & Screen Backing.	1
Custom DA-1000	Sq Truss; Alum, 2 ft 0 in tall x 25 ft 6 in long (435lbs)	1
LED Backlit Camdenton Lakers Logo; 7'-0" x 14'-10"	LED Backlit Camdenton Lakers Logo; 7'-0" x 14'-10"	1
OB-STATIC ID	Backlit sponsor panel 42" x 306" - 714 lbs each: top panel	1
CUSTOM SEPARATE BACKLIT AD PANELS TO MATCH SCOREBOARD LENGTH	Backlit sponsor panel 3.6 ft x 9.15 ft wide - 264 lbs each: bottom panel flanking FB-2005	2
FB-2500-W-PV-R	PanaView® Modular Football Scoreboard; Clock Section; Scoreboard Color: _____; Caption Color: _____ Digit Type: PANAVIEW Digit Color: WHITE Max Power: 250 watts/display Weight: Unpackaged 130 lbs per display; Packaged 272 lbs per display	1
Stripe; Modular Football	Stripe for Modular Football Sections	1
120VAC Trumpet Horn #55	For Outdoor Scoreboards	1
Radio Receiver	Frequency of 2.4 GHz	1
Outdoor Scoreboard Fiber Communication	Communication Type: Fiber (Cable not included) - Back-up option to Radio	1
TI-2003-A-PV for Delay of Game	PanaView® Delay of Game Timer; Set of 2; Scoreboard Color: _____ Cabinet Dimensions: 3' 0" H X 4' 0" W X 0' 8" D (Approx. Dimensions) Digit Type: PANAVIEW Digit Color: AMBER Max Power: 150 watts/display Weight: Unpackaged 65 lbs per display; Packaged 120 lbs per display	1
ID_36x48_O	3' x 4' non-backlit sponsor panel	2
AS-5010 Kit	All Sport® 5010 Control Console Kit	1
Outdoor Scoreboard Radio Communication (Transmitter)	Frequency of 2.4 GHz	1
Radio Receiver	Frequency of 2.4 GHz	2
Angle Clamp Mounting Method (A)	For 2 Tubes	1
FREIGHT	Shipping to site via Independent Carrier	1
Physical Installation	See attachment A.	1
System Startup	Final Commissioning of Equipment	1

### Services

<b>2</b>	<b>Warranty &amp; Services</b>	<b>1</b>
----------	--------------------------------	----------

## DAKTRONICS QUOTE # 602184-1-0

P1G5 - 1 Year Platinum, Additional 4 Years Gold Extended Service for 602184- 1-0 Alternate 1 Equipment	1 Year Parts and Labor, Additional 4 Years Parts Extended Service for 602184-1-0 Alternate 1 Equipment. Includes 45' lift and normal business hours labor. Reference SL-04703 for Platinum scope of services and SL-05659 for Gold scope of services.	1
Standard Video with Tricaster On-Site Training		1

**Total Price Excluding Sales Tax: \$390,642.00**

Please reference listed sales literature: DD1757027 for TI-2003-A-PV for Delay of Game, DD1923159 for Control-4 video inputs-SD/HD (Primary/Backup Player & Processor) w/ Laptop, DD1936413 for Standard Video All Sport® and DakStats RTD Input Kit, DD2216211 for FB-2500-W-PV-R, DD2216211 for FB-2504-W-PV-R, DD2259498 for DVX-1130-15HD-N-HC-288x504-120BR-LT-MR-CNTLRM-None, DD2356684 for DVNMC-144X432-6-RGB-SF-120VAC-MA-MN-WS-MR, DD2563729 for Custom RTD Frames -- Single Color Background, DD2568960 for Sponsor Feature - Animations, DD2568960 for Sponsor Feature - Static, DD2568960 for Sponsor Logo - Animations, DD2568960 for Sponsor Logo - Static, DD2568960 for Team Spirit Basketball Animations - 20, DD2568960 for Team Spirit Football Animations - 20, SL-03991 for AS-5010 Kit, SL-04370 for Outdoor Scoreboard Radio Communication (Transmitter), SL-04370 for Radio Receiver, SL-08027 for Custom DA-1000, SL-08027 for DA-1000-14, SL-08027 for DA-1000-18

Please reference listed shop drawings: DWG 1107197 for DVNMC-144X432-6-RGB-SF-120VAC-MA-MN-WS-MR

DRAFT

# DAKTRONICS QUOTE # 602184-1-0

## Alternate Equipment: 2

Item No.	Model	Description	Qty	Price
1	DVNMC-144X432-6-RGB-SF-120VAC-MA-MN-WS-MR	6mm LED Electronic Message Center  Matrix: 144 lines by 432 columns Line Spacing: 6mm Face Configuration: SF - single one sided display View Angle: 140 degrees Horizontal x 140 degrees Vertical Cabinet Dimensions: 4' 0" H X 10' 0" W X 0' 6" D (Approx. Dimensions) Max Power: 1525 watts/display Weight: Unpackaged 162 lbs per display; Packaged 265 lbs per display	1	\$38,559.00
	Control Kit #1 DVNMC w/ SCS and Laptop	Show Control Communication Kit to control 1 or more signs displaying the same content; Includes Laptop	1	
	SCS Software and Training - One-on-One webinar	Show Control Software for 1 License on 1 Computer with DVNMC/ST-2101 Player Support, Includes customized training in a live, web-based, conference call format.	1	
	Control Room Fiber Patch Panel	Control room fiber patch panel; 6 fiber	1	
	W-1490	Fiber Optic Cable; 50 µm Multimode; 12 Fiber with non-terminated ends	500	
	FREIGHT	Shipping to site	1	
	Physical Installation	See attachment A.	1	
	System Startup	Final Commissioning of Equipment	1	
<b>Services</b>				
2	Warranty & Services		1	
	P1G5 - 1 Year Platinum, Additional 4 Year Gold Extended Service for 602184-1-0 Alternate 2 Equipment	1 Year Parts and Labor, Additional 4 Year Parts Extended Service for 602184-1-0 Alternate 2 Equipment. Includes 45' lift and normal business hours labor. Reference SL-04703 for Platinum scope of services and SL-05659 for Gold scope of services.	1	

**Total Price Excluding Sales Tax: \$38,559.00**

Please reference listed sales literature: DD1757027 for TI-2003-A-PV for Delay of Game, DD1923159 for Control-4 video inputs-SD/HD (Primary/Backup Player & Processor) w/ Laptop, DD1936413 for Standard Video All Sport® and DakStats RTD Input Kit, DD2216211 for FB-2500-W-PV-R, DD2216211 for FB-2504-W-PV-R, DD2259498 for DVX-1130-15HD-N-HC-288x504-120BR-LT-MR-CNTLRM-None, DD2356684 for DVNMC-144X432-6-RGB-SF-120VAC-MA-MN-WS-MR, DD2563729 for Custom RTD Frames -- Single Color Background, DD2568960 for Sponsor Feature - Animations, DD2568960 for Sponsor Feature - Static, DD2568960 for Sponsor Logo - Animations, DD2568960 for Sponsor Logo - Static, DD2568960 for Team Spirit Basketball Animations - 20, DD2568960 for Team Spirit Football Animations - 20, SL-03991 for AS-5010 Kit, SL-04370 for Outdoor Scoreboard Radio Communication (Transmitter), SL-04370 for Radio Receiver, SL-08027 for Custom DA-1000, SL-08027 for DA-1000-14 , SL-08027 for DA-1000-18

Please reference listed shop drawings: DWG 1107197 for DVNMC-144X432-6-RGB-SF-120VAC-MA-MN-WS-MR

## Options

*Please contact your sales representative for additional information*

Team Spirit Basketball Animations - 20	Personalized Package - Your School Colors, Mascot/Logo - 3 Pointer, Swish, Defense, etc	1	\$1,900.00
--	---	---	------------

# DAKTRONICS QUOTE # 602184-1-0

## Leasing Program

If your purchase exceeds \$25,000, you may qualify for our leasing program allowing you more flexibility to spread out the cost of your Daktronics display over of a period up to five (5) years. Benefits of our leasing program include fixed rate financing, non-appropriation clause, no prepayment penalty, and customizable payment schedules. Plus, at the end of the lease, the equipment is yours to keep with no additional balloon payments.

Sample payment options as follows:

\$50,000 in total equipment cost = \$10,700 per year

\$100,000 in total equipment cost = \$21,199 per year

\$250,000 in total equipment cost = \$52,899 per year

\*\*Payments based on 5 year/annual payment in advance structure. **Leasing is subject to credit approval and agreed upon documentation with Daktronics lending partner.** Contact your Daktronics representative for additional options and details.

### Exclusions:

- |  |                       |
|--|-----------------------|
| - Power                                  | - Hoist               |
| - Technical Support/Installation Support | - Signal Conduit      |
| - Labor to Pull Signal Cable             | - Applicable Permits  |
| - Taxes                                  | - Front End Equipment |

Unless expressly stated otherwise in this Quote # 602184-1 Rev 0 or the attachments, if Daktronics performs installation of the Equipment, the price quoted does not include the following services pertaining to physical installations: digging of footings (including dirt removal), any materials fabrication, installation of steel cages, rebar, or bolt attachments, or pouring and finishing of concrete footings. Those service may be provided for an additional cost beyond the quoted price. Purchaser shall be fully responsible for any and all additional costs plus overhead in the event anything unexpected of any nature whatsoever is found while digging the footings including but are not limited to rock, water, utility lines, pipes or any other unforeseen circumstance. The Purchaser acknowledges and agrees that it is fully responsible for all site conditions.

### Installation Responsibilities:


If applicable please reference Attachment A for Installation Responsibilities.

### Ad/ID Copy Approval Process

Daktronics will process your proofs on orders that include advertising and identification panels. Your digital files and copy layouts should conform to graphic file standards document, SL-04116. The digital data files and copy layouts must be submitted at the time of your order and our proofs need to be approved two weeks prior to your initial anticipated ship date. Advertising and identification panels not receiving proof approvals in time will be shipped without copy in our standard finish.



Dennis Coffel  
PHONE: 314-477-7853  
FAX: 605-697-4746  
EMAIL: Dennis.Coffel@daktronics.com



Jerry Sikkink  
PHONE:  
FAX: 605-697-4700  
EMAIL: Jerry.Sikkink@daktronics.com

### Terms And Conditions:

The Terms and Conditions which apply to this order available on request.

- |   |  |
|---|--|
| SL-02375 Standard Terms and Conditions of Sale                  | ( <a href="http://www.daktronics.com/terms_conditions/SL-02375.pdf">www.daktronics.com/terms_conditions/SL-02375.pdf</a> ) |
| SL-02374 Standard Warranty and Limitation of Seller's Liability | ( <a href="http://www.daktronics.com/terms_conditions/SL-02374.pdf">www.daktronics.com/terms_conditions/SL-02374.pdf</a> ) |
| SL-07862 Software License Agreement                             | ( <a href="http://www.daktronics.com/terms_conditions/SL-07862.pdf">www.daktronics.com/terms_conditions/SL-07862.pdf</a> ) |
| SL-04116 Graphic File Standards                                 | ( <a href="http://www.daktronics.com/terms_conditions/SL-04116.pdf">www.daktronics.com/terms_conditions/SL-04116.pdf</a> ) |

### Acceptance:

The Undersigned has actual authority to execute this document and Daktronics, Inc is relying upon such authority.

The parties hereby acknowledge and agree that the terms and conditions contained within this Quote along with the terms and conditions of the Daktronics Standard Terms and Conditions, the Standard Warranty and Limitations of Liability, and/or the Software License Agreement (together, the "Terms and Conditions") constitute the full and final understanding of the parties regarding the sale of equipment and/or the provision of services and entirely replace and supersede any previous understanding or agreement between the parties. By executing this agreement, Purchaser acknowledges that it has had opportunity and means to review the Terms and Conditions as provided in the website addresses above. In the alternative, hardcopy of these Terms and Conditions will be provided upon request. Further it is acknowledged and agreed that the price of the equipment and/or the provision of services contained within this agreement are expressly conditioned upon Purchaser's acceptance of the Terms and Conditions without change. Any modification of the Terms and Conditions may require a corresponding change in price. Accordingly, the Purchaser acknowledges and agrees to these Terms and Conditions as evidenced by its attestation below.

\_\_\_\_\_  
Customer Signature

\_\_\_\_\_  
Print Name

\_\_\_\_\_  
Date

\_\_\_\_\_  
Title





## ATTACHMENT A Indoor, Outdoor

Responsible Party		Description
Daktronics	Customer	
	✓	1. Provide payment and performance Bond.
	✓	2. Secure necessary sign permits.
✓		3. Secure necessary construction permits.
	✓	4. Provide existing utility drawings.
✓		5. Removal of existing equipment.
✓		6. Removal of existing structure (excluding footings).
✓		7. Disposal of existing equipment.
✓		8. Disposal of existing structure (excluding footings).
✓		9. Generate and issue site specific electrical and signal drawing submittals for scoring, message center, video equipment.
✓		10. Generate and issue site specific equipment shop drawing and attachment detail submittals for scoring, message center, video equipment.
	✓	11. Provide approval of all engineering drawings, electrical drawings, shop drawings, equipment locations, color renderings, and ad copy layouts.
	✓	12. Provide soil investigation report at time of order.
	✓	13. Customer is responsible to ensure the existing structure/building is adequate, including any necessary modifications, for the installation of the Equipment, including but not limited to (i) obtaining certified engineer drawings to the extent required by law and (ii) providing Daktronics, upon reasonable request, documentation relating to the existing structure and modifications necessary for Daktronics perform its work.
	✓	14. Unobstructed access to equipment and control room installation site until display is 100%.
	✓	15. Mark location of the new Equipment as delineated in the quote.
✓		16. Locate public underground utilities.
	✓	17. Locate private underground utilities.
	✓	18. Landscaping to include all.
	✓	19. Provide camera-ready artwork for ad panels, and logos at time of order.
✓		20. Provide all required floor protection.
✓		21. Provide all landscape protection, track, sidewalk, path, site restoration, and/or sprinkler system repair work.
✓		22. Site clean-up after Daktronics work.
✓		23. Crating and shipping of all equipment to facility via common or independent carrier.
✓		24. Accept, lift, unload, and inspect all scoring, message center, video equipment and control equipment from carrier.
	✓	25. Provide storage of scoring, message center, video equipment and control equipment in a safe, dry, and secure location until installation.
✓		26. Provide Equipment attachment hardware.
✓		27. Install Equipment attachment hardware.

# DAKTRONICS QUOTE # 602184-1-0

✓		28. Excavation of drilled pier foundation(s) including spoils removal. Placing and finishing of concrete for foundations. (Note: Daktronics assumes class 3 soil per the International Building Code to determine footing / structure estimates included in this quotation. In the event rock, water, or if soil conditions other than class 3 soil are encountered (including soft soils, unstable or collapsing soils, expansive soils, organic materials, or anything unexpected condition is encountered, the Customer will be responsible for any additional costs, plus overhead and profit of 20%).
✓		29. Steel fabrication and erection of structural columns.
✓		30. Steel fabrication and erection Equipment mounting sub-structure.
✓		31. Paint new support structure.
✓		32. Lift and mount Equipment listed in this quotation.
	✓	33. Provide primary power feed up to and including five (5) feet off grade on structure in the form of transformer and electrical disconnect with over current protection per all applicable electrical codes and regulations. Note: Maximum voltage of 120 volts line to neutral for all display systems.
✓		34. Provide secondary power conduits, distribution panel, power cable and power hook-up from the five (5) feet off grade on structure to all Daktronics supplied load centers/termination panel at/within the Equipment.
	✓	35. Provide primary power conductors for each piece of Equipment up to and including a J-box three (3) feet of Equipment location. Primary power shall include; transformer, electrical disconnect, panel board with over current protection per all applicable electrical codes and regulations. Provide all required breakers based on the Equipment electrical loads. Note: Maximum voltage of 120 volts line to neutral for all display systems.
✓		36. Provide secondary power conduits, conductors and power hook-up from the J-box within five (5) feet off grade on structure to all Daktronics supplied load centers/termination panel at/within the Equipment.
	✓	37. Provide and install signal cable conduit, with pull string, from control location to each outdoor Equipment location. Conduit to be located five (5) feet off grade on structure, as delineated in the electrical and signal drawings.
✓		38. Mount and install fiber patch panel as required by electrical and signal drawings.
	✓	39. Provide and install signal cable conduit, with pull string, from control location to each camera location, as delineated in the electrical and signal drawings.
✓		40. Installation of Daktronics provided radio/wireless receiver hardware at the equipment location.
	✓	41. Provide all required building (wall/roof) penetrations for the installation of Daktronics provided wireless bridge and/or radio transmitter components at the control location. Mount Daktronics provided wireless bridge and/or radio transmitter components to the building in accordance with manufacturers recommendations. Building penetration location shall provide clear line-of-sight to the equipment. Provide all conduit, with pull string, from control location equipment to the building penetration location.
✓		42. Furnish signal cable as delineated on the quote. Note: Furnished signal cable is NOT plenum rated.
✓		43. Labor to pull all new signal cable (and remove existing cable, if required).
✓		44. Terminate signal cable at control location and scoring, message center, video Equipment.

# DAKTRONICS QUOTE # 602184-1-0

	✓	45. Provide a climate controlled and secure control room for all control systems. Normal operating temperature should be between 40° to 90° Fahrenheit (4° to 32° Celsius). Normal operating humidity should be less than 80% non-condensing. Storage temperature should be between -10° to 105° Fahrenheit (-23° to 41° Celsius). Storage humidity should be less than 95% non-condensing. Keep computers and monitors out of direct sunlight during storage. Allow control equipment taken out of storage to return to operating temperature range prior to turning it on (24 hours recommended).
	✓	46. Provide high speed internet connection to control room equipment.
	✓	47. Required power outlets on clean dedicated circuit(s) for all scoring, message center, video and control equipment.
✓		48. Provide computer(s) for control software.
✓		49. Unpack, set-up, hook-up, and testing of control system.
✓	✓	50. Provide personnel for maintenance and operator training.
✓		51. Perform maintenance training during installation.
✓		52. Perform operator training.
✓		53. Perform final systems testing and commissioning.
	✓	54. Final acceptance, per DF-1252.
✓	✓	55. Walk-thru inspection at Substantial Completion and identification of punchlist items
✓		56. Completion of punch list items.

NOTE: All change order work performed by Daktronics or Daktronics subcontractor will be performed at cost plus 20% overhead and profit.

DRAFT